BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Placing of CCTV Camera (Large Block Spots and SWM Plants) in ward no. 7 Byatarayanapura

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	2	Outdoor PLZ IP Cameras with 20 X optical zoom with controller along with suitable mounting system (PTZ Pan Tilt and Zoom feature is availbale in this camera can be contolled by the software for pan Tilt and zoom feature at the contol center and can be programmed to view at different angles and zoom level continuosly. It operates at day and night and the viewing distance at clarity is about 100 metres	No	78462	Rupees Seventy Eight Thousand Four Hundred Sixty Two Only
2	2	Bracket (Corner Mount / Pole Mount/ Wall Mount) for mounting the PTZ camera.	No	4267	Rupees Four Thousand Two Hundred Sixty Seven Only
3	2	Outdoor 50 Meter IP Cameras with IR & Mounting Bracket (with IR for day and night vision and can provide a viewing distance of 50 metres)	No	21160	Rupees Twenty One Thousand One Hundred Sixty Only
4	2	Bracket and weatherproof Installation kit for 50 Meter IP Camera	No	1545	Rupees One Thousand Five Hundred Forty Five Only
5	2	Outdoor 30 Meter IP Cameras with IR & Mounting Bracket (with IR for day and night vision and can provide a viewing distance of 30 metres)	No	15260	Rupees Fifteen Thousand Two Hundred Sixty Only
6	2	Bracket and weatherproof Installation kit for 30 Meter IP Camera	No	1491	Rupees One Thousand Four Hundred Ninety One Only
7	2	32 Channel NVR DS 7732 NI- E4 (with 4 Sata Option) the control box and the recording device to connect upto 32 devices, can be cascaded to provide additional cameras	No	66982	Rupees Sixty Six Thousand Nine Hundred Eighty Two Only
8	2	12 TB NAS Box for Back up (NET GEAR) provides storage for the recorded data for quick view back and storage	No	257420	Rupees Two Hundred Fifty Seven Thousand Four Hundred Twenty Only
9	2	4 TB SATA for storage and fitted in the NVR Device for storage	No	22850	Rupees Twenty Two Thousand Eight Hundred Fifty Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
10	2	A suitable sheet metal control panel to house site Equipments (Weather Proof) The power supply and the ethernet connectivity adaptor is stored in this box.	No	1526	Rupees One Thousand Five Hundred Twenty Six Only
11	2	Power supply for the camera.	No	461	Rupees Four Hundred Sixty One Only
12	2	Ethernet Switch for connectivity to Internet and Camera	No	950	Rupees Nine Hundred Fifty Only
13	1	Supply & Laying of Network and Power Cables from Camera to the control Box.	No	389	Rupees Three Hundred Eighty Nine Only
14	2	Video Manager Application Software for Display and Management of Camera on Video Display.	No	20000	Rupees Twenty Thousand Only
15	1	Installation, Erection & commissioning charges	No	5060	Rupees Five Thousand Sixty Only

13/02

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

13/02

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be
2 Unit rates and prices shall be quoted by the Tender in Indian rupees.
3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"DTS Approved"

Chief Engineer
Yelahanka Zone
Jnath Bangalore Mahanagara
Bangalore 92